

Cockpit positions	CL - Left Panel	C - Center Panel	CR - Right Panel
	AC - Aft Console	FC - Fore Console	OH - Overhead
	COL - Collective	CY - Cyclic	

BEFORE START

BATT switch (OH).....ON

Interior lights (OH)As des.

ANTI-COL Lights (OH)SET / As req.

TROOP WARN - ALARM & JUMP LT switches (OH).....As req.

APU switch (OH)RUN for 5”, START for 2” then RUN

APU RDY Light (OH)Verify ON

APU GEN switch (OH)ON

MFDs (CL, C, CR)SET

MFD1: VSDFUEL (Half)	MFD4: VSD/HSDH (Half)
MFD2: POWERTRAIN (Full)	MFD5: WCA (Full)
MFD3: POWERTRAIN (Full)	

PWR XFER 1 & 2 switches (OH)2x ON

B/U PWR switch (OH).....ON

Searchlights (COL).....As req.

Parking Brake (C)SET

ENGINE START

L MAIN FUEL pumps switches (OH).....2x ON

XFEED switch (OH)OPEN

ENG 1 COND lever (OH).....GROUND

ENG 1 START switch (OH)PRESS & HOLD until $N_G \geq 12\%$

Once 1st engine stabilized $N_G \geq 50\%$

ENG 2 COND lever (OH).....GROUND

ENG 2 START switch (OH)PRESS & HOLD until $N_G \geq 12\%$

Once both engines stabilized $N_G \geq 50\%$

POWER TRAIN page (MFD).....Verify all transmissions ≥ 7 psi

ENG COND levers (OF).....2x FLIGHT

GEN 1 & 2 switches (OH)2x ON *(Wait 2" inbetween)*

APU GEN switch (OH).....OFF

PWR XFER 1 & 2 switches (OH).....2x OFF

APU switch (OH)OFF

POST-START

All FUEL PUMP switches (OH)8x ON

XFEED switch (OH)CLOSE

Radar Altimeter (CR).....SET

Radios.....SET & TUNED

Exterior LightsAs req.

TAXI

SWIVEL switch (AC)STEER / As req.

SYSTEM SEL (AFCS) knob (FC).....OFF / As req.

TAXI (CONTINUED)

ChocksREMOVE

Tail ramp & Cabin door.....As req.

Parking Brake (C)RELEASE

SWIVEL switch (AC)LOCK when ground taxi complete

BEFORE TAKEOFF

Parking Brake (C)As req.

SYSTEM SEL (AFCS) knob (FC).....BOTH / As req.

MFDs (CL, C, CR)SET

Flight Director (CDU, FC)SET

BEFORE LANDING

Parking Brake (C)As req.

SWIVEL switch (AC).....As req.

SHUTDOWN

Flight Director (CY)DECOUPLED

Flight controlsNEUTRALIZE

SWIVEL switch (AC).....As req.

Parking Brake (C)SET

Heater Function switch (OH).....OFF

SearchlightsOFF & STOW

SYSTEM SEL (AFCS) knob (FC)OFF

ChocksPLACE

APU switch (OH)RUN for 5”, START for 2” then RUN

APU RDY Light (OH)Verify ON

APU GEN switch (OH)ON

GEN 1 & 2 switches (OH)2x OFF

PWR XFER 1 & 2 switches (OH).....2x OFF

ENG COND levers (OF)2x GROUND *2' cooldown*

XFEED switch (OH)CLOSE

All FUEL PUMP switches (OH).....8x OFF

ENG COND levers (OF)2x OFF

B/U PWR switch (OH)OFF

After rotors stopped PWR XFER 1 & 2 switches (OH)2x OFF

APU GEN switch (OH).....OFF

APU switch (OH)OFF

Interior & Exterior lightsOFF

BATT switch (OH)OFF